



Website WWW.KENSTRUCKREPAIR.com

Email Sales@KENSTRUCKREPAIR.com

Truck Repair, Inc.

Office 815•697•2361

Fax 815•697•2522

Interstate-57 Exit 302 ◀ 400 North Oak - P.O. Box 37 ▶ Chebanse, Illinois 60922

**Quote, Specification, Price on
2020 Titan 48ft Thinwall Walking V Floor Trailer w/ Removeable Bolt On Roof
Spring Ride – Keith Floor**

Customer application	Compactor Garbage
Base model	48-2-TW-VF – Removeable Bolt on Roof
Style	Straight
Wall configuration	
Front	To Suit Garbage Application
Sides	7-14" + 1-6" to Suit Garbage Application & upgrading to HD panels
Rear Door	Compactor SDSWG, Inner SDSWG, manually operated with Side grabs @59 5/8" from ground - See Note #3
Overall length	48ft
Overall width	102" Nominal
Overall height	13' 1" Approx to top of sidewalls
King pin location	36" WELD IN
Upper coupler	5/16" THK Steel– Set @ 48" high
Number of Axles	
Primary	Two (2) – See Note #1
Axles	5" round - .580 wall - straight Spindle
Axle track	77"
Suspension	Reyco 21B @ 50" w/ inner wear plates & 3 leaf springs
Location of spreads	65.5" from rear
Hub/drum assembly	10 Stud Duralite – Hub Pilot/Centrifuse Drum
Disc wheel size	8.25 x 24.5
Rims	STEEL- Std. Duty – Pre-painted White
Tires	
Brand	Goodyear
Size	11R24.5
Tread	G661
Ply	16
Quantity	8
Axle layout	FRONT -Prim -50 - Prim -65.5 - REAR
Oil seals	SKF
Lubricants	Oil-Std 80W-90
Brakes	
ABS	2S/1M Meritor Wabco
Slack adj.	Haldex Auto
Cam Enclos	All Axles – C/W Dust Shields
Lift kits	None
Lift controls	None
Frame width	48"
Rear bumper	Narrow, Steel, Offset, Push, Underride – See Note #3

	Option #1	Tow hooks are incorporated into bumper
	Option #2	Bumper extension channels
	Option #3	None
Tire carrier		None
Landing gear		Holland Mark 5 - Self leveler foot
Top rail		Titan Tapered, V1
Top cross tube		Need sidewalls prepped with spigot for future spring – but no spring But no spring bar provided.
Floor crossmembers		12” Centers
Keith walking floor kit		Running floor II – 3” Dia Cylinders – 10” stroke
Slat model & width		2654-18-slat alum v slat (impact) 2650 trough-2652 bearing
Slat wear strips		8’ wear strips at rear
Continuous bearing		None
Side wall wear plates		12’ x 3/16” x full height rear sidewall wear plate
Front access door		None
Tarp style/Roof		NO Tarp – Removable Bolt on Roof made in (3) sections – See Note #4
Tarp header		None
Tarp basket		None
Tarp hooks		None
Axle fender		None
Hyd fitting	Pressure	1” quick coupler – Male – See Note #2
	Return	1” quick coupler – Female – See Note #2
Mud flaps	Style	Titan black rubber
	Location	Rear
Mud flap – Landing gear		None
Paint	Body – color	Natural aluminum
	Run – gear	Titan black
	Hub / drum	Same as running gear
	Rims or Disc	Pre-painted White
Light package		3 markers per side (includes corner, mitre, & midturn) At Rear: 3 per side, 4” dia in door, & 5 rect. clearance at top
	Option #1	Lights in door
	Option #2	None
Access	Catwalk	None
	J-Ladder Frt	None
	J-Ladder Rear	None
	Steps Frt out	Rung style steps up driverside
	Steps Frt in	None
	Steps Rear	None

Additional specifications:

- 1) Axles are to be inverted
- 2) Add 111" hose at front. Install hose hanger bracket roadside beside rung style step between the 4th & 5th step approx.
- 3) No center pin.
 - i. Dimension from ground to bottom of inner door opening is (64 15/16").
 - ii. Add rubber pucks to the door same as we did for WO 4849 to prevent side wall damage. See rear view compactor dimension
 - iii. Side grabs are to be installed for compactor hook up. (No center pin hook up) 59 5/8" from ground to center of side grab
- 4) Install Removable roof mad of NGHD 1 1/2" panels to suit garbage compactor application that can be removed in 3 sections. Prep sidewall for future spring bar installation (spring bar not provided).
- 5) Add a solid aluminum push block to rear door driverside for loader to close door. (replace UHMW push block with aluminum one)

Estimated volume: 123 cu yds

List Price

\$ 109,960.67

No FET Included, FOB Chebanse, IL

No State Or Local Tax Included

No License Or Title Fees Included